



SCOPE OF WORKS

Project: REPAIR AND REHABILITATION OF ADMIN BLDG. ROOFING

Location: SLSU-MAIN, SOGOD CAMPUS, SOGOD, SOUTHERN LEYTE

Owner: SOUTHERN LEYTE STATE UNIVERSITY

Project Duration: 60 C.D.

ITEM #	DESCRIPTION	QTY	UNIT	AMOUNT	
				Material	Labor
1.00	General Requirements	530	lot		
2.00	Roofing Works	1,314	lm		
3.00	Fabrication of End Wall	2.25	sq.m.		
4.00	Waterproofing Application	163.30	sq.m.		
	Sub-Total				

A. DIRECT COST

B. INDIRECT COST

- 1 Contingency Allow. (5% of A.1)
- 2 VAT, Taxes, Misc. (7% of A +B.1)
- 3 Contractor's Profit(10% of A+B.1)

TOTAL PROJECT COST

Prepared by:

Reviewed By:



Excellence | Service | Leadership and Good Governance | Innovation | Social Responsibility | Integrity | Professionalism | Spirituality

Project: REPAIR AND REHABILITATION OF ADMIN BLDG. ROOFING

Location: SLSU-MAIN, SOGOD CAMPUS, SOGOD, SOUTHERN LEYTE

Owner: SOUTHERN LEYTE STATE UNIVERSITY

ITEM #	DESCRIPTION/MATERIALS	QTY	UNIT	UNIT COST	Amount
1.00	General Requirements				
	Removal/Stripping-off and Hauling and/or Disposal of Existing Metal Sheets and Damaged Portion of the Roof Framing		lot		
	Chipping and disposal of collapsed parapet wall		sq.m.		
	Temporary Removal and Reinstallation of 6 PV Panels		unit		
	Sub-Total				
2.00	Roofing Works				
2.01	<i>Right Wing</i>				
	1.22m x 0.6mmthk Pre-painted, Pre-fabricated Rib-Type Roofing Sheets		l.m.		
	2.44mx0.6mm thk Pre-painted, Pre-fabricated Ridge Roll		pcs		
	2.44mx0.6mm thk Pre-painted, Pre-fabricated End-Flashing		pcs		
	2.44mx0.6mm thk Pre-painted, Pre-fabricated Fascia Cover		pcs		
	10mm Double-Sided Aluminum Insulation Foam		50m/Roll		
	#16 G.I. Tie Wire		kgs		
	Texscrew #2		pcs		
	2"x6"x1.5mm C-Purlins		length		
	1"x1"x1/4" Angle Bar		length		
	Silicone Sealant		tubes		
	Blind Rivets # 3/16 x 1/2		pcs		
	Welding rod		kgs		
	Epoxy Primer Gray		gal		
2.02	<i>Left Wing</i>				
	1.22m x 0.6mmthk Pre-painted, Pre-fabricated Rib-Type Roofing Sheets		l.m.		
	2.44mx0.6mm thk Pre-painted, Pre-fabricated Ridge Roll		pcs		
	2.44mx0.6mm thk Pre-painted, Pre-fabricated End-Flashing		pcs		
	2.44mx0.6mm thk Pre-painted, Pre-fabricated Box-Type Gutter		pcs		
	0.6mm thk Pre-painted Plain Sheets End-Capping		sheets		

Project: REPAIR AND REHABILITATION OF ADMIN BLDG. ROOFING

Location: SLSU-MAIN, SOGOD CAMPUS, SOGOD, SOUTHERN LEYTE

Owner: SOUTHERN LEYTE STATE UNIVERSITY

ITEM #	DESCRIPTION/MATERIALS	QTY	UNIT	UNIT COST	Amount
	Double-Sided Aluminum Insulation Foam		50m/Roll		
	#16 G.I. Tie Wire		kgs		
	Silicone Sealant		tubes		
	Texscrew #2		pcs		
	2"x2"x1/4" Angle Bar		length		
	Concrete Nail # 1		kgs		
	Blind Rivets 3/16 x 1/2"		pcs		
	Welding rod		kgs		
	Epoxy Primer Gray		gal		
	Sub-Total				
3.00	Fabrication of End Wall				
	2"x2" x 2mm C-Purlins		length		
	0.6mm thk Pre-painted Plain Sheets		sheet		
	2.44mx0.6mm thk Pre-painted, Pre-fabricated End-Flashing		pcs		
	Texscrew #2		pcs		
	Welding rod		kgs		
	Epoxy Primer Gray		gal		
	Portland Cement		bags		
	Wash Sand		cu.m.		
	Gravel, 3/4		cu.m.		
	Sub-Total				
4.00	Waterproofing Application				
	Flexible Cementitious Waterproofing		gal		
	Portland Cement		bags		
	Fine/graded sand		cu.m.		
	Paint Roller		pcs		
	Sub-Total				

A. DIRECT COST

1 Material Cost

2 Labor Cost

SUB-TOTAL

Project: REPAIR AND REHABILITATION OF ADMIN BLDG. ROOFING

Location: SLSU-MAIN, SOGOD CAMPUS, SOGOD, SOUTHERN LEYTE

Owner: SOUTHERN LEYTE STATE UNIVERSITY

ITEM #	DESCRIPTION/MATERIALS	QTY	UNIT	UNIT COST	Amount
B.	INDIRECT COST				
1	Contingency Allow. (5% of A.1)				
2	VAT, Taxes, Misc. (7% of A +B.1)				
3	Contractor's Profit(10% of A+B.1)				

SUB-TOTAL

TOTAL PROJECT COST

Prepared by:

Reviewed By: